Lab 2

Ben Frazer*

February 20, 2022

Contents

1.1 Alternator 2 Setup 3 Experiments 3.1 synchronisation 3.1.1 Procedure 3.2 Open circuit Test 3.2.1 Procedure 3.2.2 Results 3.3 Short Circuit Test 3.3.1 Procedure 3.3.2 Results 3.3.4 Load Tests	1
3 Experiments 3.1 synchronisation 3.1.1 Procedure 3.2 Open circuit Test 3.2.1 Procedure 3.2.2 Results 3.3 Short Circuit Test 3.3.1 Procedure 3.3.2 Results	2
3.1 synchronisation 3.1.1 Procedure 3.2 Open circuit Test 3.2.1 Procedure 3.2.2 Results 3.3 Short Circuit Test 3.3.1 Procedure 3.3.2 Results	2
3.1.1 Procedure 3.2 Open circuit Test 3.2.1 Procedure 3.2.2 Results 3.3 Short Circuit Test 3.3.1 Procedure 3.3.2 Results	2
3.2 Open circuit Test 3.2.1 Procedure 3.2.2 Results 3.3 Short Circuit Test 3.3.1 Procedure 3.3.2 Results	2
3.2.1 Procedure	2
3.2.2 Results	2
3.3 Short Circuit Test 3.3.1 Procedure 3.3.2 Results	2
3.3.1 Procedure	3
3.3.2 Results	3
3.3.2 Results	3
3.4 Load Tests	3
	3
3.4.1 Setup (Steps 1-2)	3
3.4.2 Test 1 - Generating with unity power factor (Zero Q)- (Step 3)	4
3.4.3 Test 2 - Generating at rated current (Positive Q) - (Step 4)	5
3.4.4 Test 3 Generating at rated current (Negative Q) - (Step 5)	5
4 Deductions	6
4.1 Synchronous Impedance Plot	6
line-spacing: 0.1;	
1 Equipment	
• Dc Power Supply	
Model Transmission Line	
• Multi-meters	
• Synchronization unit	

^{*2704250}F@student.gla.ac.uk

1.1 Alternator

Table 1.1: Alternator Nameplate Values

Stator Voltage (V)	Stator Voltage +20% (V)	Rotor Voltage (VDC)	Power (W) @1500 rpm
41.5	49.8	24	50

2 Setup

- Load Switch Disabled
- 3-Phase power supply connected to load switch
- 3-Phase Wattmeter connected to the three phase supply
- Three Phase supply connected to the stator of the synchronous motor
- Dc power supply connected to synchronous machine rotor
- DC Power supply switched on
- DC Power to motor increased gradually
- DC Motor begins to turn Drive train at $V \approx 8-11Vdc$

3 Experiments

3.1 synchronisation

3.1.1 Procedure

- Dc voltage increased until DC motor is running at synchronous speed ≈ 1500rpm
- Second DC Supply turned on to exit the rotor
- Excitation Current increased gradually
- Generator open circuit voltage noted as changing as excitation current to the rotor is increased?
- Machine is Disabled

3.2 Open circuit Test

3.2.1 Procedure

- Name Plate Rating of the Synchronous machine noted
- Additional 20% margin added to stator voltage rating
- DC Motor restarted
- Synchronous motor spun up to 1500rpm
- The Generator side of the synchronisation unit is disconnected
- \bullet The Rotor excitation current is set to 0A
- The rotor excitation current is increased in steps of 0.5A until the measured stator voltage reaches 49.8V (calculated according to: $1.2 \times V_{\text{stator Name-Plate}}$).
 - for each 0.5A step the synchronous speed was controlled to 1500rpm by adjusting the supply to the DC Motor
 - for each step of 0.5A the open circuit generator voltage was recorded

3.2.2 Results

Table 3.1: Stator Line voltage Vs rotor Excitation current for open circuit test

I _{rot} (A)	$V_{Line}(V)$
0.050	6.71
0.100	12.10
0.150	17.10
0.201	23.10
0.251	28.90
0.302	34.60
0.350	39.60
0.402	44.70
0.451	49.00
0.501	52.90

3.3 Short Circuit Test

3.3.1 Procedure

- The leads leaving the 3 Phase wattmeter which were disconnected Last experiment are now connected together effectively short-circuiting the Generator
- The rotor field supply is set to zero and the supply is switched on
- The DC Motor is turned on and the DC voltage supply is adjusted until the speed of the drive train is at 1500 rpm
- Rotor field excitation current gradually increased in steps of 0.05A
 - rotor speed is kept constant at 1500rpm for each step
 - for each step the current flowing out of the generator terminals is noted

3.3.2 Results

Table 3.2: Stator Current Vs rotor excitation current for short circuit test

I _{rot} (mA)	I _{stat} (mA)
0	0
52	0
101	350
150	496
200	639
250	786
299	930
325	1010

3.4 Load Tests

3.4.1 Setup (Steps 1-2)

- 1. Synchronisation (Step 1)
 - Synchronous machine used as a generator into an infinite bus
 - A 3-Phase Power supply is used to simulate the grid

- Load switch is set to Off on the synchronisation unit
- The Synchronisation unit is set to Intensity
- The leads between the Synchronisation unit and the 3-Phase Wattmeter are reconnected
- The DC supply to the DC motor is switched on and the supply voltage is adjusted until the speed of the generator reaches 1500rpm
- The DC Rotor supply is now turned on and the current is adjusted until the generator line voltage is 45V which is the same amplitude of the 3-Phase supply
- The thee phase supply is now turned on
 - It is noted that the three lights on the synchronisation unit now begin to flash at \approx0.5Hz
- The motor speed is then adjusted by varying the DC motor current until the lights cease to flash.
- The Load switch is now set to On
 - it is noted that the lights now Cease to flash meaning the synchronous machine is now synchronised with the 3-Phase supply
- 2. Zero Apparent power flow (Step 2)
 - The Rotor field excitation current and the DC Motor Current (its torque) is adjusted to minimise the AC stator current
 - the generator is neither motoring or generating with losses supplied by the DC motor (no real power is flowing between the grid and the synchronous machine)

3.4.2 Test 1 - Generating with unity power factor (Zero Q)- (Step 3)

1. Procedure

- The Current to the DC motor is increased until the stator current is roughly $2/3 I_{nom}$ which is calculated as 464mA
 - I Guess this will be primarily real power
- the rotor excitation current is then adjusted until the stator current is minimised
 - cancelling out the reactive power by altering the magnitude of the EMF?
- Once the stator current is minimised, the following are recorded
 - Final stator current
 - Prime mover input power
 - rotor excitation current
 - Terminal voltage
 - Power factor
 - rotor angle
- the synchronous speed of the rotor is then measured with the lamp thing

2. Results

Table 3.3: Mesurements while operating at zero reactive power

Measurand	Value
Field Excitation Current	478 mA
Line Current	$417~\mathrm{mA}$
Line Voltage	$47.2~\mathrm{V}$
Active Power	$33.4~\mathrm{W}$
Power Factor	1
Prime Mover Input Power	$105.67~\mathrm{W}$
Rotor (load) Angle	330°

3.4.3 Test 2 - Generating at rated current (Positive Q) - (Step 4)

1. Procedure

- The rotor excitation current is increased until the stator current reaches its nominal value.
 - the Prime-mover torque is kept constant
- The following are recorded:
 - Final stator current
 - Prime mover input power
 - rotor excitation current
 - Terminal voltage
 - Power factor
 - rotor angle

2. Results

Table 3.4: Mesurements while operating at rated current with negative reactive power

Measurand	Value
Field Excitation Current	638 mA
Line Current	$689~\mathrm{mA}$
Line Voltage	$47.5~\mathrm{V}$
Active Power	$36.0~\mathrm{W}$
Power Factor	0.63
Prime Mover Input Power	$104.48~\mathrm{W}$
Rotor (load) Angle	150°

3.4.4 Test 3 Generating at rated current (Negative Q) - (Step 5)

1. Procedure

- 24:29
- DC Motor Power is kept constant
- Rotor excitation current is reduced to the value measured in step 3: 478mA
- Rotor excitation current is continually reduced until the stator current reaches its nominal value
- The following are recorded at this point:
 - Final stator current
 - Prime mover input power
 - rotor excitation current
 - Terminal voltage
 - Power factor
 - rotor angle
- the synchronising switch is opened and all power supplies are turned off

2. Results

Table 3.5: Mesurements while operating at rated current and positive negative power

Measurand	Value
Field Excitation Current	334 mA
Line Current	$692~\mathrm{mA}$
Line Voltage	$47.6~\mathrm{V}$
Active Power	$42.8~\mathrm{W}$
Power Factor	-0.75
Prime Mover Input Power	$110.2~\mathrm{W}$
Rotor (load) Angle	150°

4 Deductions

4.1 Synchronous Impedance Plot




Figure 4.1: Synchronous Impedance Calculated according to Equation ref:equation.